



Chailey School

Labour only full MEP Package

- Full MEP comprised of the installation of both domestic and cat5 water services throughout the 3story school extension. Servicing the 12 new toilet blocks, science suites and kitchen.
- Installation of steel heating pipework, air source heat pump pipework, domestic services, over 75 rads and soil and vent pipework to all the bathrooms, labs and kitchens.
- The installation of a brand new plant room, inclusive of water tanks, dosing pots, buffer vessels, heat exchangers, circulations pumps and booster sets.
- Electrically we installed all of the buildings small power including sockets and classroom dados, plus air source heat units, AHU's and associated equipment.
- We facilitated the extension of the mains incoming power by installing additional armoured cable supply to the new floorspace
- New suspended PIR LED luminaires were installed via a gripple suspension system

Value: £420,000